A+ Framers, Inc.

From: Lisa Roth <lisa.roth14@gmail.com>
Sent: Monday, July 20, 2026 1:43 PM
To: A+ Framers, Inc.
Subject: Fwd: Mabe
Attachments: 9C8A9848-B455-484D-9AFB-7338B361074A.jpeg; measurements MABE.pdf

The owner of Naples Family Dentist (the Mabe's) Live in Kalea Bay and would like a bid on the following: Once our demo guys remove drywall and base (They would REMOVE ALL DRYWALL to soffit)von this wall then you would:

- Add wall in front of existing wall leaving niche with space around the TV and sound bar.
- Wall size is 96" tall by 246-1/2" wide.
- Build wall out 6.5 " plus drywall
- Add backing for TV and Floating shelf
- Drywall niche and wall. There will be two end corner beads as well
- Approximate Niche size 92 wide x 70 tall (leaving niche 6.5" deep)
- ELECTRICIANS will have to pull wires through to new wall prior to drywall.

So basically the job is - build wall and come back and hang and finish.

Please bid job in owner's names. We will back the job being paid.

PAUL and YVETTE MABE
13945 OLD COAST ROAD #1503
Naples, FL 34110

thanks so much,

Lisa Roth
Cell: (239) 289-2890
Fax: (239) 598-4844